

# Standard Specification for Mixing Plants for Hot-Mixed, Hot-Laid Bituminous Paving Mixtures<sup>1</sup>

This standard is issued under the fixed designation D 995; the number immediately following the designation indicates the year of original adoption or, in the case of revision, the year of last revision. A number in parentheses indicates the year of last reapproval. A superscript epsilon ( $\epsilon$ ) indicates an editorial change since the last revision or reapproval.

*This standard has been approved for use by agencies of the Department of Defense.*

## 1. Scope

1.1 This specification covers requirements for plants suitable for producing hot-mixed, hot-laid bituminous paving mixtures.

1.2 The values stated in inch-pound units are to be regarded as the standard.

## 2. Referenced Documents

### 2.1 ASTM Standards:

C 136 Test Method for Sieve Analysis of Fine and Coarse Aggregates<sup>2</sup>

D 8 Terminology Relating to Materials for Roads and Pavements<sup>3</sup>

D 140 Practice for Sampling Bituminous Materials<sup>3</sup>

## 3. Terminology

3.1 For definitions of terms see Terminology D 8.

3.2 *Definitions of Terms Specific to This Standard:*

3.2.1 *batch plant, n*—a manufacturing facility for producing bituminous paving mixtures that proportions the aggregate and bituminous constituents into the mix by weighed batches, adds bituminous material by either weight or volume, and mixes the blend.

3.2.2 *continuous mix plant, n*—a manufacturing facility for producing bituminous paving mixtures that continuously proportions the aggregate and bituminous constituents into the mix by a continuous volumetric proportioning system without definite batch intervals.

3.2.3 *drum mix plant, n*—a manufacturing facility for producing bituminous paving mixtures that continuously proportions aggregates, heats and dries them in a rotating drum, and simultaneously mixes them with a controlled amount of bituminous material. The same plant may produce cold-mixed bituminous paving mixtures without heating and drying the aggregates.

## 4. Requirements for All Plants

4.1 *Uniformity*—The plant shall be capable of uniformly combining and mixing various sizes of aggregate from stockpiles, reclaimed asphalt pavement, if required, and bituminous material.

4.2 *Equipment for Preparation of Bituminous Material:*

4.2.1 Tanks for storage of bituminous material shall be equipped for heating the material, under effective and positive control at all times, to the temperature required in the paving mixture specifications. Heating shall be by steam or oil coils, electricity, or other means such that no flame shall contact the heating tank.

4.2.2 The circulating system for the bituminous material shall be of adequate capacity to provide proper and continuous circulation between storage tank and proportioning units during the entire operating period.

4.2.2.1 The discharge end of the bituminous material circulating pipe shall be kept below the surface of the bituminous material in the storage tank to prevent discharging the hot bituminous material into the open air.

4.2.2.2 All pipe lines and fittings shall be steam or oil-jacketed or otherwise properly insulated to prevent heat loss. When the bituminous material is emulsified asphalt, provisions should be made in the bitumen transfer system that will enable the operator to turn off or reduce the heat media from all lines, pumps, and jacketed bituminous material buckets as soon as the system is open and circulating properly.

4.2.3 Storage tank capacity shall be such as to ensure continuous operation of the plant and uniform temperature of the bituminous material when it is introduced into the aggregate. Tanks shall be calibrated accurately to 100-gal (378.5-L) intervals and shall be accessible for measuring the volume of bituminous material at any time.

4.2.4 A sampling tap, complying with the requirements of Practice D 140, shall be provided in the bituminous material feed lines connecting the storage tanks to the bituminous control unit.

4.2.5 When filled or native bituminous materials are used, means shall be provided for agitation to maintain a uniform product.

4.3 *Mineral Filler*—Adequate dry storage shall be provided for mineral filler, when required, and provision shall be made for accurate proportioning.

<sup>1</sup> This specification is under the jurisdiction of ASTM Committee D-4 on Road and Paving Materials and is the direct responsibility of Subcommittee D04.23 on Plant-Mix Bituminous Surfaces and Bases.

Current edition approved Sept. 10, 1995. Published November 1995. Originally published as D 995 – 48 T. Last previous edition D 995 – 95a.

<sup>2</sup> *Annual Book of ASTM Standards*, Vol 04.02.

<sup>3</sup> *Annual Book of ASTM Standards*, Vol 04.03.

4.4 *Cold Aggregate Feeder*—The plant shall be provided with mechanical means for uniformly feeding the aggregates into the dryer so that uniform production and temperature may be assured. When aggregates must be blended from two or more bins at the cold feed to meet the requirements of the paving mixture specifications, a synchronized proportioning method shall be provided.

4.4.1 If recycling capability is required, the plant shall be equipped with mechanical means for feeding the desired weight of reclaimed asphalt pavement into the mix. Facilities shall be provided for obtaining samples of the reclaimed asphalt pavement.

4.5 *Dryer*—A dryer of satisfactory design capable of drying and heating the aggregate to the moisture and temperature requirements of the paving mixture specifications shall be provided.

4.6 *Bituminous Control Unit:*

4.6.1 Satisfactory means, either by weighing or metering, shall be provided to obtain the proper amount of bituminous material. Accuracy of the metering devices shall be within 1.0 % of the actual weight being measured when that weight has been determined using another measuring device and shall be within 0.5 % when that weight has been determined using test weights. Bituminous material scales shall conform to 8.5.

4.6.2 Suitable means shall be provided, either by steam or oil jacketing, or other insulation, for maintaining the specified temperature of the bituminous material in the pipe lines, meters, weigh buckets, spray bars, and other containers or flow lines.

4.7 *Thermometric Equipment:*

4.7.1 An armored recording thermometer of suitable range shall be fixed in the bituminous material feed line at a suitable location near the discharge at the mixer unit.

4.7.2 Approved recording thermometers, pyrometers, or other recording thermometric instruments shall be fixed at the discharge chute of the dryer and, when applicable, in the hot fines bin to register and record automatically the temperature of the heated aggregate or heated mixture.

4.8 *Emission Controls:*

4.8.1 A dust collecting system shall be provided. The system shall be made to waste the material so collected, or to return all or any part uniformly to the mixture.

4.8.2 Other emissions, such as smoke but excepting water vapor, shall be controlled to be in compliance with applicable limits.

4.9 *Surge and Storage Bins*—If bins are used for surge or storage, they shall be such that mixture drawn from the bin meets the requirements of the paving mixture specification.

4.10 *Safety Requirements:*

4.10.1 Adequate and safe stairways to the mixer platform shall be provided if applicable. Guarded ladders to other plant units shall be located where required.

4.10.2 All gears, pulleys, chains, sprockets, and other dangerous moving parts shall be thoroughly protected.

4.10.3 Ample unobstructed space shall be provided on the mixing platform if applicable.

4.10.4 An unobstructed passage shall be maintained at all times in and around the truck-loading space. This space shall

be kept free of drippings from the mixing platform. A ladder or platform shall be located at the truck-loading space to permit easy and safe inspection of the mixture as it is delivered into the trucks. Overhead protection shall be provided where necessary.

## 5. Significance and Use

5.1 This specification describes the various components of batch, continuous mix, and drum mix plants. This standard is useful to help evaluate existing plants and for specifying new plants to ensure the plant is capable of producing a quality product. This standard does not address plant operation and control or mixture production.

## 6. Requirements for Plants Controlling Gradation of Hot, Dry Aggregates

### 6.1 *Plant Screens:*

6.1.1 Plants shall be equipped with plant screens located between the dryer and hot aggregate bins and shall have adequate capacity and size range to separate the heated aggregate into the sizes required for proportioning so that they may be recombined consistently within the specification limits.

6.1.2 The nominal maximum size aggregate in the fines bin shall be specified. The screen type and size shall be determined by the operator. No aggregate shall be larger than the maximum specified.

6.1.3 Control shall be based on frequent bin samples tested in accordance with Test Method C 136. Aggregate in each bin, including mineral filler, shall be combined in proper proportions, and the composite shall be checked for compliance with the paving mixture specifications.

### 6.2 *Hot Aggregate Bins:*

6.2.1 Hot-bin storage of sufficient capacity to ensure uniform and continuous operation shall be provided. Bins shall be divided into the specified number of compartments arranged to ensure separate and adequate storage of appropriate fractions of the aggregate.

6.2.2 Each compartment shall be provided with an overflow chute of such size and at such a location to prevent any backing up of material into other compartments or into contact with the screen.

6.2.3 Bins shall be equipped with “tell-tale” devices to indicate the position of the aggregate in the bins at the lower quarter points. An automatic plant shut-off shall be provided to operate when any aggregate bin becomes empty.

6.2.4 Adequate and convenient facilities shall be provided for obtaining aggregate samples from each bin.

## 7. Requirements for Plants Controlling Gradation of Cold, Damp Aggregates

7.1 *Maximum Aggregate Size*—Oversize aggregate shall be rejected by suitable methods or devices before the aggregate enters the cold feed, or by plant screens complying with 6.1.

### 7.2 *Cold Feed Bins:*

7.2.1 Cold feed bins for storing aggregates prior to proportioning shall be equipped with “tell-tale” devices to indicate the position of the aggregate in the bins at the lower quarter points. An automatic plant shut-off shall be provided to operate when any aggregate bin becomes empty or the flow from any bin gate becomes restricted.

7.2.2 Adequate and convenient facilities shall be provided for obtaining samples of the full flow of aggregate from each cold feed bin and from the total cold feed.

7.2.3 Adequate and convenient facilities shall be provided for diverting aggregate flow into trucks or other suitable containers to check the accuracy of the aggregate delivery system.

7.2.4 Control shall be based on frequent samples from each cold-feed bin and the total cold feed tested by Test Method C 136. Results of total cold-feed samples shall be checked for compliance with the paving mixture specifications.

## 8. Requirements for Batch Plants

8.1 *Control of Aggregate Gradation*—The plant shall be equipped to control aggregate gradation in accordance with the requirements of either Section 6 or Section 7.

### 8.2 *Weigh Box or Hopper:*

8.2.1 Means shall be provided for weighing aggregate from each bin into a weigh box or hopper, suspended on scales, and ample in size to hold a full batch.

8.2.2 The weigh box or hopper shall be supported on fulcrums and knife edges that will not easily be thrown out of alignment or adjustment.

8.2.3 Gates, both on the bins and the hopper, shall not leak.

### 8.3 *Aggregate scales:*

8.3.1 Scales for any weigh box or hopper may be either beam or springless-dial type and shall be of standard make and design. The accuracy of the weighing device shall be within 1.0 % of the actual weight being measured when that weight has been determined using another measuring device and shall be within 0.5 % when that weight has been determined using test weights.

8.3.2 The change in load required to alter noticeably the position of rest of the indicating element (or elements) of a nonautomatic indicating scale shall not be greater than 0.1 % of the nominal scale capacity.

8.3.3 Beam type scales shall be equipped with a device to indicate that the required load is being approached. This device shall indicate at least the last 200 lb (91 kg) of the load.

8.3.4 Graduation intervals for either beam or dial scales shall not be greater than 0.1 % of the nominal scale capacity. Scale graduations and markings shall be plainly visible.

8.3.5 On dial scales, parallax effects shall be reduced to the practical minimum with clearance between the indicator index and scale graduations not exceeding 0.06 in. (1.5 mm).

8.3.6 Scales shall be equipped with adjustable pointers for marking the weight of each material to be weighed into the batch.

8.3.7 Not less than ten test weights, each of 50-lb (22.7-kg) nominal weight and each stamped with its actual weight to within  $\pm 0.05$  %, shall be provided for the purpose of testing and calibrating the scales. For each scale a suitable cradle or platform shall be provided for applying the test loads. The test weights shall be kept clean and conveniently located for calibration of the scale.

### 8.4 *Bituminous Material Bucket:*

8.4.1 If a bucket is used, it shall be large enough to handle a batch in a single weighing.

8.4.2 The filling system and bucket shall be of such design,

size, and shape that the bituminous material will not overflow, splash, or spill outside the bucket during filling and weighing.

8.4.3 The time required to add the bituminous material shall not exceed 20 s. Where the quantity of bituminous material is metered, provision shall be made to check the delivery of the meter by actual weight.

8.4.4 The bucket shall be steam or oil-jacketed or equipped with properly insulated electric heating units. It shall be arranged to deliver the bituminous material in a thin uniform sheet or in multiple sprays over the full length of the mixer.

8.5 *Bituminous Material Scales*—Scales for the weighing of bituminous material shall meet the requirements for aggregate scales, as specified in 8.3 except a device to indicate at least the last 20 lb (9.1 kg) of the approaching total load shall be provided. Beam-type scales shall be equipped with a tare beam or adequate counterbalance for balancing the bucket and compensating periodically for the accumulation of bituminous material on the bucket.

### 8.6 *Mixer Unit for Batch Method:*

8.6.1 The plant shall include a batch mixer of an approved twin-shaft pugmill type capable of producing a uniform mixture.

8.6.1.1 The mixer shall be designed to provide means of adjusting the clearance between the mixer blades and liner plates to ensure proper and efficient mixing.

8.6.1.2 If not enclosed, the mixer box shall be equipped with a dust hood to prevent loss of dust by dispersion.

8.6.1.3 The mixer shall be constructed to prevent leakage of the contents.

8.6.1.4 Mixer discharge shall not cause appreciable segregation.

8.6.2 The mixer shall be equipped with a positive means for governing mixing time and an accurate time lock to control the operation of a complete mixing cycle by locking the weigh-box gate after the charging of the mixer until the closing of the mixer gates at the completion of the cycle; it shall lock the bituminous material bucket throughout the dry-mixing period and shall lock the mixer gate throughout the dry- and wet-mixing periods.

8.6.2.1 The dry-mixing period is defined as the interval of time between the opening of the weigh-box gate and the application of bituminous material. The wet-mixing period is the interval of time between the start of the application of bituminous material and the opening of the mixer gate.

8.6.2.2 The timing control shall be flexible and capable of being set at intervals of not more than 5 s throughout cycles up to 3 min.

8.6.2.3 If required by the specifications, a mechanical batch counter shall be installed as part of the timing device and shall be designed to register only completely mixed batches.

### 8.7 *Automation of Batching:*

8.7.1 If required by the specifications, an automatic weighing, cycling, and monitoring system shall be installed as part of the batching equipment.

8.7.2 The system shall include equipment for accurately proportioning the various components of the mixture by weight or by volume in the proper order, and equipment for controlling the cycle sequence and timing of mixture operations. There

shall be auxiliary interlock cut-off circuits to interrupt and stop the automatic batching operations whenever an error exceeding the acceptable tolerance occurs in proportioning.

8.7.3 *Accuracy*—The automatic proportioning system shall be capable of consistently delivering materials within the full range of batch sizes within the following tolerances:

Batch aggregate component	Total Batch Weight of Paving Mix, %
Mineral filler	±1.5
Bituminous material	±0.5
Zero return (aggregate)	±0.1
Zero return (bituminous material)	±0.5
	±0.1

The electrical circuits for the above delivery tolerances of each cut-off interlock shall be capable of providing the total span for the full allowable tolerance for maximum batch size. Tolerance controls shall be automatically or manually adjustable to provide spans suitable for less than full-size batches (Note 1). The automatic controls and interlock cut-off circuits shall be capable of being consistently coordinated with the batching scale or meter within an accuracy of 0.2 % of the nominal capacity (Note 2) of said scale or meter throughout the full range of the batch sizes.

NOTE 1—If separate tolerance controls are not provided for the batching of mineral filler, it will be necessary to reduce the aggregate tolerances to ± 0.5 % for those batches requiring mineral filler.

NOTE 2—The term “nominal capacity” of a scale or meter where referred to herein is defined as the maximum quantity which the scale or meter is capable of measuring.

### 8.8 *Recording of Batching:*

8.8.1 If required by the specifications, an automatic graphic or digital record shall be produced for each batch of bituminous concrete indicating the proportions of each aggregate component, mineral filler, and bituminous material. Such records of the batches shall be further identified through a print of day and date. Bituminous material proportions shall be recorded either as weight or volume. If recorded as volume, the record shall be either in gallons at 60°F (16°C), gallons converted to weight in pounds, or actual gallons with an additional recording of bituminous material temperature.

8.8.2 If a digital tape or ticket recorder is used, it shall record the proportions as indicated on the batching scale or meter within an accuracy of 0.5 % of maximum batch size.

8.8.3 If graphical recording is used, it shall be designed so that the stylus will traverse at least 9 in. (229 mm) of the recorder width for the total aggregate weight and maximum bituminous material weight or volume; the preceding based on maximum batch size.

8.8.3.1 The charts shall be designed so that all quantities, including zero can be read directly and shall have a resolution of at least ten lines per inch. The chart speed shall be such that individual aggregate weights, when batched cumulatively, can be clearly identified.

8.8.3.2 The recorder shall record the proportions as indicated on the batching scale or meter within an accuracy of 0.5 % of the maximum batch size.

## 9. Requirements for Continuous Mix Plants

9.1 *Control of Aggregate Gradation*—The plant shall be equipped to control aggregate gradation in accordance with the

requirements of either Section 6 or Section 7. Accurate means of checking the proportioning of each hot bin size by weight shall be provided.

9.1.1 Hot-aggregate bins shall include interlocked feeders mounted under the bin compartments. The interlocked feeders shall be equipped with a dust-proof revolution counter with minimum graduations of one tenth of a revolution. The mix proportions shall be set up on the basis of pounds (or kilograms) of each aggregate bin size per revolution.

9.1.2 Each bin shall have a feeder mechanism, subject to control by positive mechanical means, to control the rate of flow of aggregate drawn from each respective bin compartment. Where the gate orifice-type feeder is used, it shall have at least one dimension adjustable by positive mechanical means. Locks shall be provided on each gate. Calibrated gages with minimum graduations of not more than 1/10 in. (2.5 mm) shall be provided for each gate to establish gate openings.

9.1.3 When added mineral filler is specified, a separate bin and feeder shall be furnished with its drive interlocked with the aggregate feeders.

9.1.4 Means shall be provided to establish the rate of flow in pounds (or kilograms) per revolution by scale weight.

9.2 *Weight Calibration of Bituminous Material and Aggregate Feed*—The plant shall include a means of calibrating gate openings and bituminous material flow by means of weight test samples in pounds (or kilograms) per revolution.

9.2.1 The aggregate fed out of the bins through individual orifices shall be bypassed into suitable test boxes, and each compartment material shall be confined in individual test receptacles or compartments.

9.2.2 Accessories shall be supplied so that the aggregate in each compartment may be weighed separately.

9.2.3 Test containers shall be of convenient size to obtain a composite weight at least 600 lb (273 kg).

9.3 *Synchronization of Aggregate and Bituminous Material Feed*—Satisfactory means shall be provided to afford positive interlocking or mechanical control between the flow of aggregate through the gates and the flow of bituminous material through the meter or other proportioning device. Means shall be provided to check the rate of flow of the bituminous material by scale weight per revolution.

9.4 *Mixer Unit for Continuous Method*—The plant shall include a continuous mixer of an approved twin-shaft pugmill-type and shall be capable of producing a uniform mixture within the permissible job mix tolerances.

9.4.1 The paddles shall be adjustable for angular position on the shafts and reversible to retard the flow of the mix.

9.4.2 Mixers shall be equipped with discharge hoppers or other facilities to prevent segregation during discharge.

9.4.3 The mixer shall carry a manufacturer’s plate giving the net volumetric contents of the mixer at the several heights, inscribed on a permanent gage.

9.4.4 Charts shall be prepared giving the rate of aggregate feed per revolution and per interval of time at the plant operating speed.

9.4.5 Continuous mixers not complying in all respects with the above requirements, but capable of producing a uniform mixture within the job mix tolerances, will be considered for

approval and may be approved.

9.4.6 The weight per unit volume relationship of the coated loose mix shall be determined and the pugmill capacity at operating height shall be determined by means of the volume gage on the side of the mixer.

9.4.7 Positive means for governing mixing time shall be provided. Mixing time shall be determined from the following equation:

$$\text{Mixing time, s} = \frac{\text{pugmill dead capacity, lb(kg)}}{\text{pugmill output, lb(kg)/s}} \quad (1)$$

### 9.5 Automation of Continuous Mixing Plants:

9.5.1 If required by the specifications, devices capable of automatically sampling and weighing the quantity of each hot-bin aggregate size and sampling, weighing, or metering the bituminous material fed to the pugmill during either a known number of revolutions of the plant or a known interval of time shall be installed as part of the plant equipment. In addition, each aggregate hot bin, mineral-filler bin, and the bituminous material feed line shall have interlock circuits such that the plant operations will be stopped if either aggregate or bituminous material flow is discontinued or reduced.

9.5.2 The plant shall proportion each size of aggregate to the pugmill with such accuracy that the weight of material from each hot bin shall not deviate from the design value by an amount more than 1.5 % of the total weight of bituminous paving mixture delivered per revolution or interval of time. Where the separate addition of mineral filler is required, it shall be added so as not to deviate more than 0.5 % of the total weight of bituminous paving mixture per revolution or interval of time. The bituminous material shall be added so as not to deviate more than 0.1 % of the total weight of bituminous paving mixture per revolution or interval of time.

9.5.3 The scales or meters, or both, used to determine the quantities of aggregates and bitumen per revolution or interval of time shall be accurate to within 0.20 % of their nominal capacities. The aggregate sampling device shall have a capacity of at least 1 lb for each ton per hour of plant output capacity or 100 lb (45.3 kg) which ever is greater.

### 9.6 Recording of Continuous Plants:

9.6.1 When required by the specifications, each plant shall have an automatic graphic or digital recorder for recording the weights of samples of each hot-bin aggregate size and bituminous material, either individually or cumulatively. In addition to the recording of sample quantities, the time of sampling identified by a time and date accurate to the nearest minute shall also be recorded.

9.6.2 If a digital tape or ticket recorder is used, it shall be capable of accurately recording weights to 0.1 % of the nominal capacity of the weighing system.

9.6.3 If graphical recording is used, it shall be designed so that the stylus will traverse at least 9 in. (229 mm) of the recorder width for the maximum aggregate sample weight and maximum bituminous material weight. The charts shall be designed so that all quantities, including zero, can be read directly and shall have a resolution of at least 10 lines per inch (25.4 mm). The chart speed shall be such that individual aggregate weights, when batched cumulatively, can be clearly identified.

9.6.4 A digital recorder shall be installed as part of the platform truck scales. The recorder shall produce a printed digital record on a ticket of the gross and tare weights of the delivery trucks along with a time and date print for each ticket. Provisions shall be made so that scales may not be manually manipulated during the printing process. In addition, the system shall be so interlocked as to allow printing only when the scale has come to rest. The scales and recorder shall be of sufficient capacity and size to weigh accurately the heaviest loaded trucks or tractor trailers that are used for the delivery of bituminous paving mixtures from the plant.

## 10. Requirements for Drum-Mix Plants

10.1 *Control of Aggregate Gradation*—The plant shall be equipped to control aggregate gradation in accordance with the requirements of Section 7.

### 10.2 Aggregate Delivery System:

10.2.1 The total cold aggregate feed shall be weighed continuously by an approved belt scale. The accuracy of the weighing device shall be within 1.0 % of the actual weight being measured when that weight has been determined using another measuring device and shall be within 0.5% when that weight has been determined using test weights.

10.2.2 Provisions shall be made for introducing the moisture content of the total cold feed into the belt weighing signal and correcting wet aggregate weight to dry aggregate weight.

10.2.3 An automatic digital record of the dry weight of aggregate flow shall be displayed, recorded, and totaled in appropriate units of weight and time at least once every 5 min of plant operation, and on demand, at least once every minute of plant operation for a period of at least 5 min.

10.2.4 When mineral filler is specified, a separate bin and feeder shall be provided with its drive interlocked with the aggregate feeders.

### 10.3 Bituminous Material System:

10.3.1 Satisfactory means shall be provided to assure positive interlock between dry weight of aggregate flow and the flow of bituminous material through an approved meter. The interlock shall be capable of adjusting the flow of bituminous material to compensate for any variation in the dry weight of aggregate flow.

10.3.2 An automatic digital record of the flow of bituminous material shall be displayed, recorded, and totaled in appropriate units of volume or weight and time at least once every 5 min of plant operation, and on demand, at least once every minute of plant operation for a period of at least 5 min. The digital record of bitumen flow shall be coordinated with the digital record of dry aggregate flow at the point at which the bitumen is discharged into the aggregate.

10.4 *Drum-Mix Plant*—The drum-mix plant shall be of satisfactory design, capable of drying and heating the aggregate to the moisture and temperature requirements set forth in the paving mixture specifications, and capable of producing a uniform mixture of aggregates and bituminous material. A surge or storage system complying with 4.9 shall be provided.

**11. Keywords**

11.1 asphalt plants; batch plants; bituminous mixing plants; bituminous paving mixtures; continuous mix plants; drum mix plants

*The American Society for Testing and Materials takes no position respecting the validity of any patent rights asserted in connection with any item mentioned in this standard. Users of this standard are expressly advised that determination of the validity of any such patent rights, and the risk of infringement of such rights, are entirely their own responsibility.*

*This standard is subject to revision at any time by the responsible technical committee and must be reviewed every five years and if not revised, either reapproved or withdrawn. Your comments are invited either for revision of this standard or for additional standards and should be addressed to ASTM Headquarters. Your comments will receive careful consideration at a meeting of the responsible technical committee, which you may attend. If you feel that your comments have not received a fair hearing you should make your views known to the ASTM Committee on Standards, 100 Barr Harbor Drive, West Conshohocken, PA 19428.*